

## **Addendum #1**

### **Bid 2014-71 Master plumber for House-to-Line Water and Sewer Connections Project "TCDP Contract #713015 in Colonia Pueblo Nuevo**

1. Bid Form has been redone to include a change on line #3. The cost of per cleanout x (8 avg.) x 14 homes has been included. The extended price should include the cost of the 14 homes.
2. Questions
  - a. When a plastic septic tank is removed does the contractor have to also dispose of the plastic tank?  
Yes, the contractor will be expected to dispose of the plastic septic tank; cost is to be included (item #4 on the Price Bid Form).
  - b. Any contractor requesting a copy of the drawings provided by the City of Laredo may contact Imelda Pena at 956-523-4605; [ipena@webbcountytexas.gov](mailto:ipena@webbcountytexas.gov)
  - c. Inspections will be conducted through the office of the Webb County engineer (Luis Perez Garcia). Contractor will contact Imelda Pena and/or Luis Perez Garcia and make arrangements. It is expected that these will be conducted within 24 hours of request to the engineer. This will help minimize the time the trench is left open.
  - d. The question of the availability of funds to replace damages (such as a sidewalk) was asked. Imelda Pena will review the grant and be ready to address the issue at the pre-construction meeting.
  - e. Right of entry will be a joint effort. It can be acquired by Imelda Pena or the selected contractor.
  - f. Completion date for all 14 homes is expected to be within 180 days of the Notice to Proceed.
  - g. Original invoices may be turned in to Imelda Pena who will verify that work is billed as performed and as agreed to on the contract.
  - h. It may be necessary to provide additional linear footage when connecting different bathrooms or sinks within the home, given that not all pipes currently in existence are always connected to each other. When such is the case the contractor should review the additional work with Imelda Pena prior to performing such work.

**Bid Form**  
(Please use official "Bid Form" for bid amounts)

**PRICING:**

Unit price includes purchase of materials, labor and equipment, i.e. in-place cost.

Bidders shall provide a unit price for the services requested in these bid specifications.

1. Price per liner foot to install a three quarter (3/4) inch water line as identified in this bid;  
per liner foot \$ \_\_\_\_\_ x (30 avg.) x **14 homes** (approx.) \$ \_\_\_\_\_

2. Price per liner foot to install a four (4) inch (schedule 40) wastewater line;  
per liner foot \$ \_\_\_\_\_ x (30 avg.) x **14 homes** (approx.)  
\$ \_\_\_\_\_

Based on topography the trench depth can be between 3-12 feet in depth.

3. Cost per cleanout (one at the dwelling, one at the tap, one every 50-feet and  
one at every 45° or 90° turn) per clean out \$ \_\_\_\_\_ x (8 avg.) x **14 homes** \$ \_\_\_\_\_

4. Price to remove and remediate septic tank (1000 gallon tank)  
(amount over 1,000 will be prorated) \$ \_\_\_\_\_

5. Cost per gallon of effluent removed & disposed  
per gallon \$ \_\_\_\_\_ x (900 gal. avg.) x **14** (approx.) \$ \_\_\_\_\_

6. Price to remove and remediate cesspool \$ \_\_\_\_\_

7. Price to remove and remediate pit privy \$ \_\_\_\_\_

8. Price per cubic yard to fill a remediated an open pit  
\$ \_\_\_\_\_ per cubic yard x (10 yd avg.) x **14 (approx)** \$ \_\_\_\_\_

9. Lowering of Sewer Tap  
(8-10ft. avg. depth) (other depths will be prorated) \$ \_\_\_\_\_

10. Installation of new Tap [when allowed/required by City of Laredo]  
Water: \$ \_\_\_\_\_

Sewer: (8-10ft. avg. depth) \$ \_\_\_\_\_

11. Installation of "T" Connection For A Second Water  
Service Connection \_\_\_\_\_ x 14 (approx.) \$ \_\_\_\_\_

12. Installation of "Y" Connection For A Second Sewer Service Connection  
\_\_\_\_\_ x 14 (approx) \$ \_\_\_\_\_

**Total**  
\$ \_\_\_\_\_